

2080.11.29

योजनाको नाम:- मलेसिया टोलमा सडक ग्राभेल तथा मर्मत कार्य
ठेगाना : गौरिगंगा नगरपालिका -०८, कैलाली

(BILL OF QUANTITIES)

S.N.	Description	Unit	Quantity	Rates		Amount (Nrs)	Remarks
				In Figure	In Words		
A	General						
i	Providing and installation of project signboards with size of 1.2 x 1.0 m as per specification and instruction of engineer [110]	Ps	1.00	1500.00		1500	
ii	Off site verification Lab testing of materials as required by the engineer's representative	Ps	1.00	5000.00		5000	
					Total	6500	
B	Constructions						
2	Scarifying Existing road Surface to a Depth of 50 mm by Manual Means, Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications.	m2	2100.00				
3	Excavation For Cross Drainage Works in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. all types of Soil by Mechanical Means .	m3	90.00				
4	Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications.	m3	105.00				
8	Providing and lying Stone Masonry work in cement mortar 1:6 in structure complete as per Drawing and Technical Specifications Random Rubble Masonry	m3	10.50				

संज्ञाको नाम:- मलेसिया टोलागा सडक प्रभोल तथा मर्मत कार्य
 प्रमाण : मलेसिया नगरपालिका -०८, कैलाली

मलेसिया टोलागा
 नगरपालिका
 कैलाली

2080.11.29

(BILL OF QUANTITIES)

S.N	Description	Unit	Quantity	Rates		Amount (Nrs)	Remarks
				In Figure	In Words		
10	Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical 600 mm internal dia.	Rm	2.50				
11	Providing and laying granular Sub-Base on prepared surface, mixing at OMC, and compacting to achieve the desired density, Specifications By Mechanical means	m ³	420.00				
Total							
Total Cost with Ps & Construction							
At @ 13% of Total							
Grand Total							

On Behalf of Firm
 Signature :
 Name of Firm:
 Seal :
 Name of Authorized Person:
 Permanent Address :
 Phone :
 Date :