

Gaurigangaa Municipality
Office of Municipal Executive
Chaumala, Kailali
Sudurpaschim Province

Bill of Quantity(BOQ)

F/Y:2082/083

Name of Project:- Construction of pipe culvert
Location:- Gauriganga 08 Badhaipur

S.No.	Description of Items	Unit	Total Quantity	Rate in figure	Rate in Words	Amount (NRs.)	Remarks
1.00	SITE CLEARANCE WORKS:Removal of dismantled debris, and removal of top soil vegetation if any including bushes etc. The ground should be levelled and ready for setting out of the proposed building all complete	sqm	60.00				
2.00	Earthwork excavation in all types of soil average depth of excavation including shoring, dewatering etc all complete as per specification & instruction.	cum	27.12				
3.00	EARTH FILLING WORKS: Earth filling with granular soil including packing in 150mm, layer watering and well compaction by ramming of each layer up to proper level & dressing, all complete	cum	16.27				
4.00	STONE SOLING WORKS: Providing and laying Dry-stone soling in foundation work including levelling etc. complete. 150 mm stone soling in foundation	cum	6.77				
5.00	Plain cement concret PCC(1:3:6) in foundation, floors etc. with cement, sand and crussed aggregate of 10 mm to 38mm gauge including mixing with mixture machine & compaction by vibrator, laying in line & level with curing all type of works complete as per specifications & instructions	cum	10.46				
6.00	STONE MASONRY WORK: Stone masonry work in sub-structure and super structure of abutments, wing walls and cut-off walls with 1:6 cement sand mortar including stones of approved quality in perfect line & level and properly packing the joints & curing the works with all complete.	cum	16.35				



गौरिगंगा नगरपालिकाको
नगर कार्यपालिकाको
द्वारा जारी प्रविष्टि
संख्या: २०७३

(Handwritten signature)



सुदूरपश्चिम प्रदेश
 कैलाली जिल्ला
 नगर कार्यपालिकाको कार्यालय
 धरमपुरी, कैलाली
 २०७३

(Handwritten signature)

7.00	PCC FOR RCC WORKS: Structural concrete (1:1.5:3 or M20 grade) with cement sand and crushed aggregate in any form, size, shape and level for all reinforced cement concrete including all formwork, mixing, laying, compacting, curing and finishing excluding centering shuttering and cost of reinforcement all complete	cum	5.98		
8.00	TOR STEEL WORK: Fixing for steel reinforcement grade 1 conforming to I.S. 1786-1985 in RCC work including cleaning, cutting, bending, placing in position and binding with no.16 swg annealed binding wire all complete.	kg	577.23		
9.00	Pointing work in 1:3 cement sand mix ratio : (DN - 37 - C - c)	Sqm	10.40		
10.00	HDP pipe provide in weep hole @ 1000mm c/c	kg	33.87		
11.00	12:5 Plaster on Facing Side of Head Wall	sqm	11.41		
12.00	Hume Pipes (NP3 Class) 1200mm dia	Rm	15.00		
13.00	Notice Board	Nos	1.00	1000.00	1000.00
14.00	Lab Test as per Site Incharge	Nos	1.00	3500.00	3500.00
				Sub total amount	
				Vat amount(13%)	
				Grand total	
IN WORDS:-					
Authorized Signature :-					
Name of form:-					
Deignation:-					
Authorized Name:-					
Office Seal:-					
Date:-					