


प.सं.:२०८१/०८२ च.नं.: 9629



फोन नं४१८०५९-०९१: .,४१८०६० वेवसाइट:www.gaurigangamun.gov.np ईमेल-info.gaurigangamun@gmail.com

मिति:-२०८१/१०/०४

विषयः दररेट पेश गर्ने बारे सूचना । (दोस्रो पटक प्रकासित मिति:-२०८१/१०/०४)

श्री सरोकारवाला सबै

उपरोक्त सम्बन्धमा यस नगरपालिकाको कार्यालय अन्तर्गत तपसिलका कार्य गर्नु पर्ने र सो कार्य दरभाउपत्र (कोटेसन) मार्फत गर्नुपर्ने भएकाले उक्त कामको लागी संलग्न BOQ अनुसार आफुले गर्न सक्ने दररेट भरी ७ (सात) दिन भित्र यस कार्यालयमा पेश गर्न हुन जानकारी गराईन्छ ।

सि.न.	वडा नं. १ गौरीगंगा आर्यघाट	जम्मारकम (मु.अ.कर सहित) रु.	BOQ खरिद गरि पेश गर्ने अन्तिम मिति र समय	पेश भएका दरेरट खोल्ने समय	
		४,९९,९९९. ८ ९/-	२०८१/१०/१० गते अपरान्ह १२:०० वजे भित्र	२०६१/१०/१० दिउँसो १:०० बजे	

पेश गर्नु पर्ने कागजात:-

- 9. दररेट पेश निर्माण व्यवसायिले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धिको लिखित निवेदन सहित निवकरण भएको फर्म / कम्पनि दर्ता प्रमाण पत्रको प्रतिलिपि, निवकरण भएको व्यवसाय दर्ता (निर्माण व्यवसाय ईजाजत पत्र), प्रमाणपत्र प्रतिलिपि, मु.अ.कर दर्ता प्रमाण प्रतिलिपि र आ.व. २०८०/८१ को कर चुक्ता प्रमाण पत्रको प्रतिलिपि संलग्न गरि पेश गर्नुपर्नेछ ।
- २. BOQ यस कार्यालयको वेवसाइटमा http://www.gaurigangamun.gov.np बाट डाउनलोड गर्न सिकनेछ । BOQ खरिद कार्य वाफतको रु. १००० (एक हजार) राजस्व शाखबाट बुझाएको नगदी रिसद तिरी अनिवार्य दररेट साथ पेश पेश गर्नुपर्ने छ । BOQ भरि खामबन्दी गरि वाहिरी खाममा फर्मको नाम ठेगाना र ठेका संकेत उल्लेख गरि पेश गर्नुपर्नेछ ।
- ३. BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि खामबन्दी गरी भिक्र राखि पेश गर्नुपर्नेछ केरमेट भएको दररेट (BOQ) मुल्यांइनमा समावेश गरिने छैन ।

हरीश पन्त उपसचिव

उपस्थिव गौर्गगङ्गः तगर्- । तिका भीविता नगरपालिका प्राचीलक केल्प्रासी प्राचीलक प्राचीलक प्राचीलक (HOV)

बोजनको नाम :- गीरीगंगा आर्यधाट मंगलपुर पुल नजिक ट्रस निर्माण स्वाद :- गीरिगंगा-०१, कैलाली

SEAR DO	data de			Rate (Nrs)		
SN	Description of Works	Unit	Quantity	Rate in Figure	Rate in Words 172	THE THOMPSON TO
A	Civil Work	1-11-1	15-15-2	Kate in Figure	Aute in World	खु प्रशासकीय अ
ı	Clearing and uprooting thin Vegitation grubbing their root's and disposal 25m far from the construction sites before construction and clearing the sites removing all unnessesary materials from the sites after completion the project as per instruction all completed.	m2	54			V
2	Earth work excavation in foundation and trenches in all type of soil except rock in both dry and wet conditions including back filling of excavated material, shoring and strutting whenever necessary, pumping out water from the trenches etc as directed with the lead of 50 m and lift 3m all complete.	m3	5.1272			
3	Back Fill Sand Filling, water spreading and compaction Sand filling including sprinkling water and compacting in layers as instruction all complete.	m3	14.31435			
4	Providing and laying Dry-stone soling in foundation work including levelling etc. complete. 150 mm stone soling in foundation	m3	7.495			
5	Plain cement concret PCC(1:3:6) in foundation, floors etc. with cement, sand and crussed aggregate of 10 mm to 38mm gauge including mixing with mixture machine & compaction by vibrator, laying in line & level with curing all type of works complete as per specifications & instructions	m3	7.1325			
6	M.S. iron Grill gate fixing work with redoxide painting. M.S. grill gate	Kg	25.2			
7	Stone Masonry in cement sand mortar of ratio 1;6 at all depth below and above plinth level with in perfect line & level with bonds as instructed by the project incharge, including curing all materials & labours complete as per Drawing, specifications & instructions.	m3	3,192			
8	BRICKWORK: First class Chimney made Brickwork in substructure / super structure in (1:4) cement sand mortar with approved quality bricks in perfect line & level with necessary scaffolding including wetting the bricks, properly packing the joints & curing the works with all complete.	m3	3.496			
9	PLASTERING WORK: Providing 12.5mm thick cement sand Plaster with 1:4 Cement mortar at all height on walls including chipping and hacking of concrete surface immediately after removeal of shuttering, wetting the surfaces, scaffolding, cleaning and curing all materials and labours complete as per instruction of Engineer, drawings and specification.	m2	30.4			
10	Laying and Installations of MS Black pipe Truss work with color & all necessary Materials and had had Rain	Kg	1016.6			
11	CGI Roofing work using 26 Gauge coloured CGI sheet	m2	77.35			
12	Roof ridge work using plain sheet using 26 gauge plain sheet	m	13			
13	HDPE Pipe 75 mm Diameter	Kg	7.2576			
14	Installation of Notice Board Providing and installation of Notice Board Project with size of 1.0 x 1.2 m as per specification and instruction of engineer	No.	1	1000		
_	Total					
_	Vat @ 13% of Total					
-	Grand Total					

On behalf of contractor

Contractor's Signature

Firm:

Sout

Contractor's Name

Permanent Address

Phone

Date