



प.सं.: २०८१/०८२

च.नं.: १३६८

गौरीगङ्गा नगरपालिका
नगर कार्यपालिकाको कार्यालय

चौमाला, कैलाली
नगर कार्यपालिका, कैलाली, नेपाल
सुदूरपश्चिम प्रदेश, नेपाल
२०७३

फोन नं ४१८०५९-०९९, ४१८०६०

वेबसाइट: www.gaurigangamun.gov.np

ईमेल: info.gaurigangamun@gmail.com

मिति: २०८१/०८/२७

विषय: दररेट पेश गर्ने बारे सूचना ।
(प्रथम पटक प्रकाशित मिति: २०८१/०८/२७)

श्री सरोकारवाला सबै

उपरोक्त सम्बन्धमा यस नगरपालिकाको कार्यालय अन्तर्गत तपसिलका कार्य गर्नु पर्ने र सो कार्य दरभाउपत्र (कोटेसन) मार्फत गर्नुपर्ने भएकाले उक्त कामको लागी संलग्न BOQ अनुसार आफुले गर्न सक्ने दररेट भरी ७ (सात) दिन भित्र यस कार्यालयमा पेश गर्न हुन जानकारी गराईन्छ ।

सि.न.	विवरण	जम्मा रकम (मु.अ.कर सहित) रु.	BOQ खरिद गरि पेश गर्ने अन्तिम मिति र समय	पेश भएका दररेट खोल्ने समय
१.	बडा नं. १ गौरीगंगा आर्यघाट मंगलपुरको पुल नजिक ट्रेस निर्माण	४,९९,९९९.८१/-	२०८१/०९/०३ गते अपरान्ह १२:०० बजे भित्र	२०८१/०९/३ दिउँसो १:०० बजे
२.	बडा नं. २ भागेधर टोलमा सिंचाई प्रयोजनका लागि विद्युत लाईन विस्तार	३,९९,९५८.७५/-	२०८१/०९/०३ गते अपरान्ह १२:०० बजे भित्र	२०८१/०९/३ दिउँसो १:०० बजे
३.	मोहन्याल मा.वि.मा फलसिलङ्ग निर्माण तथा बडा कार्यालय हलमा ए.सि.जडान	४९९९५२.४९/-	२०८१/०९/०३ गते अपरान्ह १२:०० बजे भित्र	२०८१/०९/३ दिउँसो १:०० बजे

पेश गर्नु पर्ने कागजात:-

- १ दररेट पेश निर्माण व्यवसायिले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धिको लिखित निवेदन सहित नविकरण भएको फर्म / कम्पनि दर्ता प्रमाण पत्रको प्रतिलिपि, नविकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायि ईजाजत पत्र), प्रमाणपत्र प्रतिलिपि, मु.अ.कर दर्ता प्रमाण प्रतिलिपि र आ.व. २०८०/८१ को कर चुक्ता प्रमाण पत्रको प्रतिलिपि संलग्न गरि पेश गर्नुपर्नेछ ।
- २ BOQ यस कार्यालयको वेबसाइटमा <http://www.gaurigangamun.gov.np> बाट डाउनलोड गर्न सकिनेछ ।
- ३ BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि खामबन्दी गरी भित्र राखि पेश गर्नुपर्नेछ केरमेट भएको दररेट (BOQ) मुल्याङ्कनमा समावेश गरिने छैन ।


२०८१/०८/२७

धर्म राज विनाडी

प्रमुख प्रशासकीय अधिकृत

प्रमुख प्रशासकीय अधिकृत

बोजनको नाम :- गौरीगंगा अर्वाघाट मंगलपुर, पुल नजिक टुस निर्माण
 स्थान :- गौरीगंगा-०१, कैलाली



26/11/2020
 2076/11/2020

SN	Description of Works	Unit	Quantity	Rate (Nrs)		Amount (Nrs)
				Rate in Figure	Rate in Words	
A	Civil Work					
1	Clearing and uprooting thin Vegetation grubbing their root's and disposal 25m far from the construction sites before construction and clearing the sites removing all unnessary materials from the sites after completion the project as per instruction all completed.	m2	54			
2	Earth work excavation in foundation and trenches in all type of soil except rock in both dry and wet conditions including back filling of excavated material, shoring and strutting whenever necessary, pumping out water from the trenches etc as directed with the lead of 50 m and lift 3m all complete.	m3	5.1272			
3	Back Fill Sand Filling , water spreading and compaction Sand filling including sprinkling water and compacting in layers as instruction all complete.	m3	14.31435			
4	Providing and laying Dry-stone soling in foundation work including levelling etc. complete. 150 mm stone soling in foundation	m3	7.495			
5	Plain cement concret PCC(1:3:6) in foundation, floors etc. with cement, sand and crussed aggregate of 10 mm to 38mm gauge including mixing with mixture machine & compaction by vibrator, laying in line & level with curing all type of works complete as per specifications & instructions	m3	7.1325			
6	M.S. iron Grill gate fixing work with redoxide painting, M.S. grill gate	Kg	25.2			
7	Stone Masonry in cement sand mortar of ratio 1:6 at all depth below and above plinth level with in perfect line & level with bonds as instructed by the project incharge, including curing all materials & labours complete as per Drawing, specifications & instructions.	m3	3.192			
8	BRICKWORK : First class Chimney made Brickwork in substructure / super structure in (1:4) cement sand mortar with approved quality bricks in perfect line & level with necessary scaffolding including wetting the bricks, properly packing the joints & curing the works with all complete.	m3	3.496			
9	PLASTERING WORK : Providing 12.5mm thick cement sand Plaster with 1:4 Cement mortar at all height on walls including chipping and hacking of concrete surface immediately after removal of shuttering, wetting the surfaces, scaffolding, cleaning and curing all materials and labours complete as per instruction of Engineer, drawings and specification.	m2	30.4			
10	Laying and Installations of MS Black pipe Truss work with color & all necessary Materials	Kg	1016.6			
11	CGI Roofing work using 26 Gauge coloured CGI sheet	m2	77.35			
12	Roof ridge work using plain sheet using 26 gauge plain sheet	m	13			
13	HDPE Pipe 75 mm Diameter	Kg	7.2576			
14	Installation of Notice Board Providing and installation of Notice Board Project with size of 1.0 x 1.2 m as per specification and instruction of engineer	No.	1	1000		
Total						
Vat @ 13% of Total						
Grand Total						

On behalf of contractor
 Contractor's Signature :
 Firm :
 Seal :
 Contractor's Name :
 Permanent Address :
 Phone :
 Date :



Gauriganga Municipality
Office of Municipal Executive
Chitwan, Nepal
सिन्धुपाल्चोक नगर कार्यपालिका

कर्मचारी
संख्या १०७९

Name Of Project: Bhageshwar Tolma Sicha Prayojanaka Lagi Bidhutiya Lain Bistar
Location: Gauriganga Municipality 02, Bhageshwar Tol (Irrigation)

SN	Description of Works	Unit	Quantity	Rate in Figure	Rate in Words	Total Amount(Nrs)	Remarks
A Cost Estimate For Materials							
1	9Mtr. PSC Pole	Nos	10.00				
2	ACSR Weasel Conductor(0.03 sq.in)	Km	2.50				
4	Shackle Insulator With Diron Set	Nos	64.00				
7	Nuts and Bolts(Full Threded, different sizes)	Kg	13.00				
8	Stay Set Complete	Set	7.00				
9	Stay Wire 7/12 SWG	Kg	35.00				
10	Stay Insulator	Nos	7.00				
				Sub Total A With VAT			
B Cost Estimate For Installation							
11	Erection of 9m PSC Pole	Nos	13.00				
12	Dismantal Of 9m PSC Pole @50%	Nos	3.00				
13	Stringing of 0.03 ACSR Weasel Conductor 1-Wire LT	Km	2.40				
14	Installation of stay set	Set	7.00				
				Sub Total B Without VAT			
				Sub Total B With VAT			
				Grand Total(A+B) With VAT			

On Behalf of Firm

Signature :

Name of Firm:

Seal :

Name of Authorized Person:

Permanent Address :

Phone :

Date :



Gauriganga Municipality
Office of Municipal Executive

Chauraha, Kailali
BILL OF MATERIALS

Name of Project :- मोहन्याल मा.वि. मा फलसिलिडिग निर्माण तथा वडा कार्यालय हलमा ए. वडा कार्यालय
Location :- Gauriganga-05, Kailali

F/Y :- 2081/082

Handwritten signature and date
2081/082

S.N.	Descriptions	Quantity	Unit	Rate		Amount	Remarks
				In Figure	In Words		
1.0	Dismantling works for brick masoanry	4.70	Cu.m				
2.0	Two coats of plastic emulsion paint	90.59	Sq.m				
3.0	Supplying and installing <u>1.2 mm plain fiber sheet</u> all complete	21.90	Sq.m				
4.0	Supplying and installing <u>6 mm thick flex O-board (water proof cement board)</u> for False Ceiling-2'*2' Plain	87.84	Sq.m				
5.0	Supplying and installing <u>1.5 TR capacity</u> wall mounted, split type, inverter type air condition all necessary wiring complete set	3.00	Set				
6.0	Surface wiring work using wooden listi or PVC pipes including plug, switch, ceiling,holder, socket, summica board or plastic board.(3/22, 7/22 NS standard cupper wire)	20.00	Point				
7.0	Supplying and installing <u>Dome Light</u>	8.00	no.				
	8" Light	10.00	no.				
	6" Light						
Total Amount							
Vat @13%							
Grand Total Amount							

IN WORDS:-

Authorized Signature :-.....
 Name:-.....
 Designation:-.....
 Firm's Name:-.....
 Office Seal:-.....
 Date:-.....