



गौरीगङ्गा नगरपालिका
नगर कार्यपालिकाको कार्यालय



मिति:- २०८१/०८/१८

प.सं.: २०८१/०८२

च.नं.:

विषय: दर रेट पेश गर्ने बारे सूचना ।
(प्रथम पटक प्रकासित मिति:- २०८१/०८/१८)

श्री सरोकारवाला सबै

उपरोक्त सम्बन्धमा यस नगरपालिका कार्यालय अन्तर्गत तपसिलको कार्य गर्नुपर्ने र सो कार्य दरभाउपत्र (कोटेसन) माफत गर्नुपर्ने भएकाले उक्त कामको लागी संलग्न BOQ अनुसार आफुले गर्न सकिने दररेट भरी ७ (सात) दिन भित्र यस कार्यालयमा पेश गर्न हुन जानकारी गराईन्छ ।

| सि.न. | विवरण | जम्मा रकम (मु.अ.कर) सहित | दररेट पेश गर्ने अन्तिम मिति र समय | पेश भएका दर रेट खोल्ने समय |
|-------|--|--------------------------------|--|---|
| १. | वडा नं. १ गोप्का कोठारी टोलको बाटो ग्राभेल तथा स्तरोउन्नती र लठैया मुक्त कमैया बस्तीमा बाटो ग्राभेल तथा स्तरोउन्नती कार्य | रु.६९८९३५.८९ | २०८१/०८/२४ गते अपरान्ह १२:०० बजे सम्म | २०८१/०८/२४ गते दिउँसो १:०० बजे सम्म |

पेश गर्नु पर्ने कागजात:-

१. दररेट पेश निर्माण व्यवसायिले अनिवार्य रुपमा दररेट पेश गर्ने व्यहोरा सम्बन्धिको लिखित निवेदन सहित नविकरण भएको फर्म / कम्पनि दर्ता प्रमाण पत्रको प्रतिलिपि, नविकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायि ईजाजत पत्र), प्रमाणपत्र प्रतिलिपि, मु.अ.कर दर्ता प्रमाण प्रतिलिपि र आ.व. २०८०/८१ को कर चुक्ता प्रमाण पत्रको प्रतिलिपि संलग्न गरि पेश गर्नुपर्नेछ ।
२. उक्त कार्यको लागी आवश्यक BOQ यस कार्यालयको वेवसाइटमा <http://www.gaurigangamun.gov.np> बाट डाउनलोड गर्न सकिनेछ ।
३. BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखि बन्द खाम भित्र राखि पेश गर्नुपर्नेछ केरमेट भएको दररेट (BOQ) मुल्याङ्कनमा समावेश गरिने छैन ।

(Handwritten signature)
२०८१/०८/१८

धर्म राज विनाडी

प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत

BILL OF QUANTITY (BOQ)

चौमालाको नगर-सडकका बायाँतर्फ बाटो अन्तर्गत नयाँ स्तरोन्नती
कार्य- गौरीगंगा-१, कैलाली

| SN | Description of Works | Unit | Quantity | Rate (Nrs) | | Amount (Nrs) |
|----|---|------|----------|----------------|---------------|--------------|
| | | | | Rate in Figure | Rate in Words | |
| A | Civil Works | | | | | |
| 1 | Scarifying Existing road Surface to a Depth of 50 mm by Manual Means, Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications. | m2 | 1400 | | | |
| 2 | Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. all types of Soil by Mechanical Means. | m3 | 113.52 | | | |
| 3 | Providing, laying, spreading and compacting embankment with borrow material as per Drawing and Technical Specifications. | m3 | 80.55 | | | |
| 4 | Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. | m3 | 1.026 | | | |
| 5 | Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications. | m3 | 0.73125 | | | |
| 6 | Providing and lying Stone Masonry work in cement mortar 1:6 in structure complete as per Drawing and Technical Specifications. Random Rubble Masonry | m3 | 1.971 | | | |
| 7 | Providing, Laying & Fitting as well as Installation Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 all Complete Works as per Drawing and Technical Specifications. 450mm internal dia. | rm | 7.5 | | | |
| 8 | Providing and laying Granular Natural River Bed Sub-Base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications By Mechanical means | m3 | 289.2 | | | |
| B) | Provisional Sum | | | Sub Total (A) | | |
| 1 | Off site verification Lab testing of materials as required by the engineer's representative | PS | 1 | 5000/- | | |
| 2 | Providing and installation of project Signboards with size of 1.0 x 1.2 m as per specification and instruction of engineer | PS | 1 | 1000/- | | |
| | Total | | | Sub Total (B) | | |
| | Grand Total | | | | | |
| | Total | | | | | |
| | Vat @ 13% of Total | | | | | |
| | Grand Total | | | | | |

On behalf of contractor

Contractor's Signature :

Firm :

Seal :

Contractor's Name :

Permanent Address :

Phone :

Date :