



सुदूरपश्चिम प्रदेश, नेपाल  
सोमनाथ, कैलाली

BILL OF QUANTITY (BOQ)

Name of project: Masuriya Khopendra dekki DodaPal Samma Sadak Pani pitch  
Location: Masuriya, 09 Kailali  
F/Y: - 2080/081

SN	Description of Works	Unit	Quantity	Rate (Nrs)		Amount (Nrs)
				Rate in Figure	Rate in Words	
<b>Part 1 : SITE CLEARANCE</b>						
1	Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications. Unit = sqm (For 600 sqm, Lead upto 30 m)	m2	312			
<b>Part 2: PAVEMENT WORKS</b>						
3.1	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications By Mechanical means	m3	285.36585			
<b>Part 3 : PROVISIONAL SUMS FOR</b>						
5.1	Off site verification Lab testing of materials as required by the engineer's representative	PS	1	5000/-		
5.2	Providing and installation of project Signboards with size of 1.0 x 1.2 m as per specification and instruction of engineer	PS	1	1000/-		
Total Construction Cost						
Vat @ 13% of Total						
Total Provisional Sum						
Grand Total						

Note:

- \* The numbers enclosed in the bracket in the particulars represent DOR Standard Specifications Section Number.
- \* All the specified material acceptance and work compliance tests as per the Standard Specification, 2001 and Quality Assurance Plan (QAP) shall be carried out by the Contractor(s) at his own cost.

On behalf of contractor

Contractor's Signature :

Firm :

Seal :

Contractor's Name :

Permanent Address :

Phone :

Date :

*(Signature)*

*(Signature)*

*(Signature)*